



TOTAL EQUIP. WEIGHT = 425 LBS
 WT. W/O DAMPENERS = 350 LBS

- NOTES:
- 1- HEIGHTS SHOWN ARE PVP STANDARDS PUMP CENTERLINE HEIGHTS CAN BE RAISED OR LOWERED.
 - 2- SWITCHES AND DAMPENERS ARE OPTIONAL. CHECK BUILD SHEETS FOR EQUIPMENT SUPPLIED.
 - 3- FLEX JOINTS NOT RECOMMENDED
 - 4- WHEN INSTALLING PUMP KEEP AREA UNDER PUMP CLEAR FOR MAINTENANCE

TOLERANCES	
FRACT.	± 0.25
DEC.	± 0.25
ANG.	± 3'

THIS DRAWING AND ALL INFORMATION IS THE PROPERTY OF
PVP PENN VALLEY PUMP CO., INC.
 998 EASTON ROAD - WARRINGTON, PA 18976
 PHONE: (215) 343-6750 FAX: (215) 343-6753

ALL INFORMATION CONTAINED IN THIS DOCUMENT IS SOLELY CONFIDENTIAL AND PROPRIETARY TO PVP. NO REUSE, REPRODUCTION, OR DISSEMINATION OF THIS INFORMATION IS PERMITTED WITHOUT THE WRITTEN CONSENT OF PVP. ANY UNAUTHORIZED USE OF THIS INFORMATION MAY BE PROSECUTED. INFORMATION CONTAINED HEREIN IS UNCLASSIFIED EXCEPT WHERE SHOWN OTHERWISE.

SCALE: 1/8"=1'-0"
 DATE: 1/19/07
 DWN. BY: []
 PLOT DATE: []

CUSTOMER: []
 LOCATION: []
 PROJECT: 2" BELT DRIVEN PIGGY BACK UNIT WITH PULSATION DAMPENERS

REV	DESCRIPTION	DATE	BY
1	EXTENDED THE SUCTION DAMPENER	3/2/2012	[]

DRAWING NO. PVD836
 SHEET 1
 REV. 1